BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41596

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work: Maintenance of water supply works to existing borewells at at Dasarahalli Village Surrounding area in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of CHETHAN P ( )	
				In Figures	In Words
1	3500	Labour Charges of lifting of non functioning submersible Pump set along with cable and GI Pipes (BWSSB SR 14-15, P-558 I-1(i)	Each	110.0	Rupees One Hundred Ten Only
2	35	Transportation of pumping machineries (P. 56 / I. 10.3.19) PRED SR (2012-13)	Each	920.0	Rupees Nine Hundred Twenty Only
3	6	A)Rewinding of Submersible Pump Sets (BWSSB SR 14-15 P-58 I-A) 10 HP	No	4800.0	Rupees Four Thousand Eight Hundred Only
4	8	(BWSSB SR 14-15 P-58 I-A) 7.5 HP	No	4000.0	Rupees Four Thousand Only
5	10	(BWSSB SR 14-15 P-58 I-A) 12.5 HP	No	5900.0	Rupees Five Thousand Nine Hundred Only
6	11	(BWSSB SR 14-15 P-58 I-A) 15.0 HP	No	5820.0	Rupees Five Thousand Eight Hundred Twenty Only
7	175	B) Replacement of Motor Parts: Pump Bowls (BWSSB SR 14-15 P-58 I-B)	No	320.0	Rupees Three Hundred Twenty Only
8	35	Intermediate Piece (I.P) With IP Leaded Bronxe bush (BWSSB SR 14-15 P-58 I-B2)	No	720.0	Rupees Seven Hundred Twenty Only
9	35	Upper Flange (BWSSB SR 14-15 P-59 I-C3)	No	345.0	Rupees Three Hundred Forty Five Only
10	35	Lower Housing (BWSSB SR 14-15 P-59 I-C4)	No	550.0	Rupees Five Hundred Fifty Only
11	130	Guide vane (BWSSB SR 14-15 P-58 I-B5)	No	180.0	Rupees One Hundred Eighty Only
12	35	Impeller Shell moulded with aluminium Bronze) (BWSSB SR 14-15 P-58 I-B6)	No	300.0	Rupees Three Hundred Only
13	40	Discharge outlet (D.O) Bearing D.O Steel Bush P. (BWSSB SR 14-15 P-58 I-B7)	No	530.0	Rupees Five Hundred Thirty Only
14	35	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) (BWSSB SR 14-15 P-58 I-B10)	No	680.0	Rupees Six Hundred Eighty Only
15	35	Pump Couping (Stainless Steel) (BWSSB SR 14-15 P-58 I-B12)	No	350.0	Rupees Three Hundred Fifty Only
16	80	Stud and Nuts (BWSSB SR 14-15 P-59 I-C8)	Each	100.0	Rupees One Hundred Only
17	20	Motor Base With Pin (BWSSB SR 14-15 P-59 I-C11)	Each	415.0	Rupees Four Hundred Fifteen Only
18	20	Starter (with one year Guarantee) P No. 55 / I No. 10.3.3 PRED SR (2012-13)	No	5075.0	Rupees Five Thousand Seventy Five Only
19	25	Rotor (with one year Guarantee) P No. 55 / I No. 10.3.6) PRED SR (2012-13)	No	4720.0	Rupees Four Thousand Seven Hundred Twenty Only
20	35	Carbon Housing P. No. 56 / I No.10.3.12 PRED SR (2012-13)	No	500.0	Rupees Five Hundred Only

Chethan P

Signature of the contractor

10/07

10/07

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of CHETHAN P ( )	
				In Figures	In Words
21	35	Thrust bearing block assembly complete with Segment bearing pad.P. No. 55 / I No.10.3.13 PRED SR (2012-13)	No	1175.0	Rupees One Thousand One Hundred Seventy Five Only
22	35	Oil Seal P. No. 54 / I No.10.2.3 PRED SR (2012-13)	No	130.0	Rupees One Hundred Thirty Only
23	35	Oil Seal Steel Bush P. No. 54 / I No. 10.2.4 PRED SR (2012-13)	No	155.0	Rupees One Hundred Fifty Five Only
24	40	D.O Bearing P. No. 44 / I No. 10.2.7 PRED SR (2012-13)	No	300.0	Rupees Three Hundred Only
25	160	Steel Bush P. No.55 / I No. 10.2.9 PRED SR (2012-13)	No	175.0	Rupees One Hundred Seventy Five Only
26	95	Allen Screw P. No.44 / I No. 10.2.9 RDPR SR (2012-13)	No	50.0	Rupees Fifty Only
27	25	Pump Key (Stainless Steel) P. No. 45 / I No. 10.2.11 RDED SR (2012-13)	No	130.0	Rupees One Hundred Thirty Only
28	20	Non – return valve (NRV) assembly complete with rubber 'O' Ring P. No. 55 / I No. 10.2.14 PRED SR (2012-13)	No	1400.0	Rupees One Thousand Four Hundred Only
29	35	Cable Guard P. No. 55 / I No. 10.2.15 PRED SR (2012-13)	No	165.0	Rupees One Hundred Sixty Five Only
30	35	Strainer P. No. 45 / I No. 10.2.15 RDED SR (2012-13)	No	165.0	Rupees One Hundred Sixty Five Only
31	35	Brass Filter P. No. 55 / I No. 10.2.17 PRED SR (2012-13)	No	275.0	Rupees Two Hundred Seventy Five Only
32	35	Labour Chargesw (Over Hauling Only) P. No. 45 / I No. 10.2.18 PRED SR (2012-13)	No	600.0	Rupees Six Hundred Only
33	35	Re-erection charges of pumping machineries including overhauling and pointing P. No. 56 / I No. 10.3.20 PRED SR (2012-13)	Each	1000.0	Rupees One Thousand Only
34	40	Lock Ring P. No. 45 / I No. 10.3.11 PREC SR (2012-13)	Each	100.0	Rupees One Hundred Only
35	35	a) Carbon Housing P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	500.0	Rupees Five Hundred Only
36	25	Top Carbon/Ferrodo padding P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	165.0	Rupees One Hundred Sixty Five Only
37	30	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush P. No. 46 / I No. 10.3.16 APRDED SR (2012-13)	Each	410.0	Rupees Four Hundred Ten Only
38	40	Circillps P. No. 45 / I No. 10.3.17 PREC SR (2012-13)	Each	60.0	Rupees Sixty Only
39	120	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete…. P No. 32/I No 3b KPWD Electrical SR 2010-11	No	180.0	Rupees One Hundred Eighty Only
40	1400	Threading of GI Pipes 50mm Dia P. No. 15 / I No.3.11.6 PRED SR (2012-13)	No	30.0	Rupees Thirty Only
41	1000	Supplying of submersible pump cable 1X3X6..0 Sq.mm (Page No. XLVII, Sl NO. 8, PWD SR-2018-19	Mtr	150.0	Rupees One Hundred Fifty Only
42	34	Supplying and fixing MCB (P.NO - XLVII, SL.NO - 19, PWD SR 18-19)	No	920.0	Rupees Nine Hundred Twenty Only
43	246.38	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 6, I.NO - 2.3, PWD SR 18-19)	Cum	320.0	Rupees Three Hundred Twenty Only

Chethan P
Signature of the contractor

10/07
10/07
Executive Engineer

Sl. No	Approved Qty.	Description	Unit	Approved Tender Rates of CHETHAN P ( )	
				In Figures	In Words
44	730	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 96, I.NO - 13.73.2, PWD SR 18-19)	Mtr	450.0	Rupees Four Hundred Fifty Only
45	246.38	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 7, I.NO - 2.11, PWD SR 18-19)	Cum	150.0	Rupees One Hundred Fifty Only
46	16	Supplying & delivery of brand 50mm Gate Valve. (PWD SR 18-19, P.NO.XLVII Sl.no, 15	No	1850.0	Rupees One Thousand Eight Hundred Fifty Only

chethan.P

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
10/07

10/07